

# TREE INVENTORY & PRESERVATION STUDY

2121 Riverside Drive West, City of Windsor

Prepared for: AGBABA HOLDINGS CORPORATION





July 2, 2024

# TABLE OF CONTENTS

ABOUT THE AUTHOR	2
INTRODUCTION	3
METHODS & OBSERVATIONS	3
RESULTS	4
Location: 2121 Riverside Drive West	5
Location: Rankin Centre Median (100 block)	13
LITERATURE CITED	19
APPENDIX	20

# ABOUT THE AUTHOR

Michael Neuheimer is the owner and president of Neuheimer Tree Care and Consulting. Michael has over 20 years of experience working in the field of Arboriculture and tree preservation. He has held numerous contracts with the City of Windsor, the City of Brampton, the local municipalities and even carried out a specialized tree inventory project for the City of Salzburg, Austria that was 22,000 trees in size. Michael has achieved a Bachelor of Science from the University of Windsor and has been a Certified Arborist with the International Society of Arboriculture (ISA) since the year 2000. He also holds credentials in Tree Risk Assessment with the ISA.

# INTRODUCTION

A Tree Inventory & Preservation Study has been prepared for Marko Agbaba, Agbaba Holdings Corporation by consultant, Neuheimer Tree Care and Consulting Inc. This study pertains to the impact of the proposed development of an apartment building for 2121 Riverside Drive West, in the City of Windsor on the surrounding trees. The scope of this study comes from a section of the City's Official Plan, whereas the purpose of the Tree Inventory and Preservation study is to:

'investigate existing tree vegetation, within and adjacent to development and determine how protection and enhancement can coincide with proposed development' (City of Windsor, 2012).

The City of Windsor has also provided Agbaba Holdings Corporation with the following comment and instructions:

"9. Tree Inventory & Preservation Study (ZBA) – (per O.P. Vol 1- SS10.2.14) Applicant is to be aware that there are 5 municipal trees near the property line along Rankin Avenue which will need to be reviewed by the City Forester and need to be preserved. Please contact Stefan Fediuk, Senior Urban Design Planner at (519) 255-6543 ext. 6025 sfediuk@citywindsor.ca with any questions for additional information.

# METHODS & OBSERVATIONS

There are a number of trees present at 2121 Riverside Drive West that were assessed for the purpose of this report. Michael Neuheimer attended the site twice to collect all the necessary information and data. He met with Marko Agbaba on site on May 28, 2024 and attended the site again on June 14<sup>th</sup>, 2024 by himself.

Trees were assessed to determine their health, structure and whether they could remain as part of the landscape or whether they would have to be removed due to conflicts with the proposed development.

Trees are routinely measured for size, by determining their diameter using an Arborist's Diameter tape, where the trunk of each tree is measured at 1.3 metres above the ground. This measurement is referred to as the trees 'Diameter At Breast Height' (DBH).

Trees were also measured for their Vitality and for their Structure. Vitality refers to the tree's overall health. Trees that had a full crown, with little to no dead wood observed in their canopy, along with a full canopy of green healthy leaves and with leaves that were free of disease or insect damage, were classified as having 'Good' vitality. Whereas, trees that had significant amounts of deadwood present, had diminished leaves, and or signs of insect and disease activity were classified as 'Fair' or 'Poor' vitality depending on the severity of the trees decline or ailments. However, no trees in this report were classified as 'Poor'.

The Structure of a tree refers to how mechanically sound the tree is, in reference to the state of its trunk, roots and branches at the time of the assessment. Trees with full a crown can appear healthy, only to find that they may be structurally flawed due to lightning strikes, storm damage,

compacted root systems, or mechanical damages done to the trunk where decay is advancing within and are now deemed as unsafe.

Finally, with the aid of a recent Plan of Survey (December 2023), all trees on site were verified for their ownership. The survey shows that all trees on site are privately owed, meaning that no portion of the trees' trunk is touching the boundary between private and municipal land.

The Forestry Act, R.S.O. 1990, c. F.26 defines trees as common property where (2) Every tree whose trunk is growing on the boundary between adjoining lands is the common property of the owners of the adjoining lands. The survey also provides a comment from the surveyor which states that 'Trees trunks shown lie completely within the subject property'. A copy of this survey is included within the Appendix section of this report.

We also observed that there are 3 City owned trees growing across from the proposed site, located in the centre median of Rankin and have been included in this report. Centre median trees are often damaged during construction activities, as they frequently serve as staging areas for heavy equipment and building materials, which can lead to their demise.

# RESULTS

Below are the details of our tree inventory for 2121 Riverside Drive West in the City of Windsor. Each table below outlines the attributes of each tree found within the study area and provides a response to the required components of the City's Tree Inventory Preservation Study guidelines within Section 10.2.14 of the Official Plan (City of Windsor, 2012).

## Location: 2121 Riverside Drive West

#### TABLE 1: 82-35 CM DBH SILVER MAPLE ATTRIBUTES

Species of Tree: Silver Maple Acer saccharinum	e,	Size: 82 cm & 35 cm DBH dominate stem)	Н (со-	Location: South west corner of property	
Canopy Vitality: Good	Struc	cture: Good	Ownership: F	Private	
Other Comments: Minor am installation; some surface ro		of deadwood in canopy; pro	bable root da	mage from sidewalk	
	The im	pact of construction in and		tress as portions of its canopy ree will cause further decline	
Possible Infrastructure Modifications: Modifications to the site plan in order to retain this tree is not recommended as this tree is entering the late stages of its life span and any gains in tree preservation will likely not be realized post construction.					
Preservation or Removal of Tree Recommended: Removal					
Best Management Practices to mitigate impact of development upon trees: NA					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.					
Details of maintenance prog	gram p	ost development: Not app	licable.		



FIGURE 1: PHOTO OF 82-65 CM DBH SILVER MAPLE

## TABLE 2: 71 CM DBH BLACK WALNUT ATTRIBUTES

Species of Tree: Black Waln	ut, Juglans nigra	Size: 71 cm DBH		Location: South west corner	
Canopy Vitality: Good	Structure: Good		Ownershi	p: Private	
Other Comments: Minor dea probable root damage from			adjacent sic	dewalk to heave upwards;	
				nd do not tolerate construction nd around this tree will lead to	
Possible Infrastructure Modifications: Modifications to the site plan in order to retain this tree is not recommended as these trees are not tolerant to construction activities.					
Preservation or Removal of Tree Recommended: Removal					
Best Management Practices to mitigate impact of development upon trees: NA					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.					
Details of maintenance prog	sram post developn	nent: NA			



FIGURE 2: PHOTO OF 71 CM DBH BLACK WALNUT

## TABLE 3: 16 CM DBH CHOKE CHERRY ATTRIBUTES

Species of Tree: Choke Che	rry, Prunus virginiana	Size: 16 cm DBH		Location: South of carport		
Canopy Vitality: Fair	Structure: Fair	·	Ownership: Private			
Other Comments: Medium infestation of the disease known as 'Black Knot of Cherry'; noticeable crown thinning						
Impact of Development on this tree: This tree is unfortunately located in the footprint of the proposed building and will have to be removed						
Possible Infrastructure Mod	lifications: Not applica	ble				
Preservation or Removal of Tree Recommended: Removal						
Best Management Practices to mitigate impact of development upon trees: NA						
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.						
Details of maintenance pro	gram post developmer	nt: Not app	licable			



FIGURE 3: PHOTO OF16 CM DBH CHOKE CHERRY

## TABLE 4: 26-40 CM DBH PAPER BIRCH ATTRIBUTES

Species of Tree: Paper Birch papyrifera	n, Betula	Size: 26-40 cm DBH		Location: North East corner of house	
Canopy Vitality: Fair	Structure: Fair		Ow	nership: Private	
Other Comments: Signs of c	crown dieback, po	ossibly from the	Bro	nze Birch Borer	
Impact of Development on this tree: This tree is unfortunately located in the footprint of the proposed building and will have to be removed					
Possible Infrastructure Mod	ifications: Not ap	plicable			
Preservation or Removal of Tree Recommended: Removal					
Best Management Practices to mitigate impact of development upon trees: Not applicable.					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.					
Details of maintenance prog	gram post develop	oment: Not app	licab	le.	



#### FIGURE 4: PHOTO OF 26-40 CM DBH PAPER BIRCH

## TABLE 5: 37 CM DBH SUGAR MAPLE ATTRIBUTES

Species of Tree: Sugar Map	e, Acer saccharum	Size: 37 cm DBH		Location: North east corner of house		
Canopy Vitality: Good	Structure: Good		Owner	ship: Private		
Other Comments: Healthy	<i>v</i> ibrant tree					
Impact of Development on this tree: This tree is unfortunately located in the footprint of the proposed building and will have to be removed						
Possible Infrastructure Mod	lifications: Not applic	able.				
Preservation or Removal of Tree Recommended: <b>Removal</b>						
Best Management Practices to mitigate impact of development upon trees: Not applicable.						
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for on either site or within the neighbourhood can be discussed.						
Details of maintenance prog	gram post developme	ent: Not app	licable.			




FIGURE 5: PHOTO OF 37 CM DBH SUGAR MAPLE

#### TABLE 6: 61 CM DBH HONEYLOCUST ATTRIBUTES

Species of Tree: Honeylocus triacanthos	st, <i>Gleditsia</i>	Size: 61 cm DBH	Location: North east corner of property		
Canopy Vitality: Good	Structure: Good		Ownership: Private		
Other Comments: Minor arr	ount of deadwoo	d present; seve	ere girdling roots		
Impact of Development on t retained.	his tree: This tree:	is free and cle	ar of this development and should be		
			protected throughout the construction ind the circumference of the canopy.		
Preservation or Removal of	Tree Recommend	led: Preservat	ion		
Best Management Practices to mitigate impact of development upon trees: Identify the tree protection zone and install tree protection fencing around the circumference of the tree's canopy to protect the root system and from heavy machinery striking the tree.					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be considered in lieu.					
Details of maintenance program post development: Decorative shredded mulch to be applied post development to help the tree retain moisture, keep machinery away from striking the bark, and to provide organic material to the soil. The tree should than be monitored for its vitality and watered weekly during times of droughty conditions in the summer and for the first 3 years post construction.					



#### FIGURE 6: PHOTO OF 61 CM DBH HONEYLOCUST

#### TABLE 7: 10 CM DBH RED MAPLE ATTRIBUTES

		<u> </u>				
Species of Tree: Red Maple	, Acer rubrum	Size: 10 cm DBH	Location: North west corner of property			
Canopy Vitality: Good	Structure: Go	bod	Ownership: Private			
Other Comments: Newer p	lanting					
Impact of Development on retained.	this tree: This t	ree is free and clea	r of this development and should be			
Possible Infrastructure Modifications: This tree should be protected throughout the construction process and tree protection fencing should be installed around the circumference of the canopy.						
Preservation or Removal of Tree Recommended: Preservation						
Best Management Practices to mitigate impact of development upon trees: Identify the tree protection zone and install tree protection fencing around the circumference of the tree's canopy to protect the root system and from heavy machinery striking the tree and compacting the soil.						
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.						
Details of maintenance pro	ogram post deve	elopment: Decorat	ve shredded mulch to be applied post			

development to help the tree retain moisture, keep machinery away from striking the bark, and to provide organic material to the soil. The tree should than be monitored for its vitality and watered weekly during times of droughty conditions in the summer and for the first 3 years post construction.



FIGURE 7: PHOTO OF 10 CM DBH RED MAPLE

## TABLE 8: 23 CM DBH NOOTKA CYPRESS ATTRIBUTES

	pecies of Tree: Nootka Cypress, Chamaecyparis nootkatensis		Location: North west of current house		
Canopy Vitality: Good	Structure: Goo	d	Ownership: Private		
Other Comments: Fine spec	cimen				
Impact of Development on this tree: This tree is unfortunately located in the footprint of the proposed building and will have to be removed					
Possible Infrastructure Mod	lifications: Not a	pplicable			
Preservation or Removal of Tree Recommended: <b>Removal</b>					
Best Management Practices to mitigate impact of development upon trees: Not applicable					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: This is a privately owned tree and compensation to the City for replacement trees is generally not a past practice. However, consideration for the funding of future tree planting for either on site or within the neighbourhood can be discussed.					
Details of maintenance program post development: Not applicable.					



FIGURE 8: PHOTO OF 23 CM DBH NOOTKA CYPRESS

## Location: Rankin Centre Median (100 block)

#### TABLE 9: 48 CM DBH NORWAY MAPLE ATTRIBUTES

Species of Tree: Norway Ma Acer platanoides	iple,	Size: 48 cm DBH	Locatior	n: Across from 126 Rankin in Centre Median	
Canopy Vitality: Good	Struc	cture: Good		Ownership: Municipal	
Other Comments: Has a gire	dling ro	oot, has a 'V' sha	ape appea	rance from pruning back of street light wire	
Impact of Development on t retained and protected.	this tre	e: This tree is fre	e and clea	ar of this development and should be	
process. Tree protection fer	ncing s otectic	hould be installe on zone. This will	ed around I keep all h	otected throughout the construction all three (3) trees growing on the centre heavy machinery and building supplies from S.	
Preservation or Removal of	Tree R	ecommended: F	Preservati	ion	
Best Management Practices to mitigate impact of development upon trees: Identify the tree protection zone and install tree protection fencing around this tree and the other two (2) trees near by.					
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: If these trees are properly protected through the creation of a tree protection zone, then the likelihood of this tree succumbing to construction activities would be very low. If these measures are in place and the trees still do succumb, a tree assessment should be conducted to see if their death was associated with this development in any way or whether they died due to some other abiotic/biotic factor.					
Details of maintenance program post development: Decorative shredded mulch to be applied post development to help the tree retain moisture, keep machinery away from striking the bark, and to provide organic material to the soil. The tree should than be monitored for its vitality and watered					

weekly during times of droughty conditions during the summer for the first 3 years post construction.



FIGURE 9: PHOTO OF 23 CM DBH NORWAY MAPLE

#### TABLE 10: 31 CM DBH RED MAPLE ATTRIBUTES

Species of Tree: Red Maple, Acer rubrum	Þ	Size: 31 cm DBH	Location: Across from 136 Rankin in Centre Media		
Canopy Vitality: Good	Struc	cture: Good		Ownership: Municipal	
Other Comments: This is th	e midd	lle tree of three (	3) trees lo	ocated on the centre median	
Impact of Development on t retained and protected.	this tre	e: This tree is fre	e and cle	ar of this development and should be	
process. Tree protection fer	ncing s otectio	hould be installe on zone. This will	ed around keep all h	otected throughout the construction all three (3) trees growing on the centre leavy machinery and building supplies from S.	
Preservation or Removal of	Tree R	ecommended: F	Preservati	ion	
-		÷ .	-	ent upon trees: Identify the tree protection the other two (2) trees near by.	
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: If these trees are properly protected through the creation of a tree protection zone, then the likelihood of this tree succumbing to construction activities would be very low. If these measures are in place and the trees still do succumb, a tree assessment should be conducted to see if their death was associated to this development in any way or whether they died to some other abiotic/biotic factor.					
Details of maintenance program post development: Decorative shredded mulch to be applied post development to help the tree retain moisture, keep machinery away from striking the bark, and to provide organic material to the soil. The tree should than be monitored for its vitality and watered					

weekly during times of droughty conditions during the summer for the first 3 years post construction.

## Neuheimer Tree Care and Consulting Inc.




FIGURE 10: PHOTO OF 31 CM DBH RED MAPLE

#### TABLE 11: 37 CM DBH NORWAY MAPLE ATTRIBUTES

Species of Tree: Norway Ma Acer platanoides	iple,	Size: 37 cm DBH	Location:	Across from 140 Rankin in Centre Median		
Canopy Vitality: Good	Struc	cture: Good		Ownership: Municipal		
Other Comments: The southern Norway Maple in the centre island						
Impact of Development on t retained and protected.	this tre	e: This tree is f	ree and clea	ar of this development and should be		
Possible Infrastructure Modifications: This tree should be protected throughout the construction process. Tree protection fencing should be installed around all three (3) trees growing on the centre median as one large tree protection zone. This will keep all heavy machinery and building supplies from being staged around the trees and over their rooting systems.						
Preservation or Removal of	Tree R	ecommended:	: Preservati	ion		
Best Management Practices to mitigate impact of development upon trees: Identify the tree protection zone and install tree protection fencing around this tree and the other two (2) trees near by.						
Provisions for tree replacement for trees that were to be retained but that were not successfully preserved: If these trees are properly protected through the creation of a tree protection zone, then the likelihood of this tree succumbing to construction activities would be very low. If these measures are in place and the trees still do succumb, a tree assessment should be conducted to see if their death was associated to this development in any way or whether they died to some other abiotic/biotic factor.						
Details of maintenance program post development: Decorative shredded mulch to be applied post development to help the tree retain moisture, keep machinery away from striking the bark, and to provide organic material to the soil. The tree should than be monitored for its vitality and watered						

weekly during times of droughty conditions during the summer for the first 3 years post construction.

## Neuheimer Tree Care and Consulting Inc.



FIGURE 11: PHOTO OF 23 CM DBH NORWAY MAPLE

# LITERATURE CITED

- City of Windsor. (2012, September 7). *Official Plan, Volume 1, SS10.2.14*. Retrieved from Chapter 10 Procedures: <u>https://www.citywindsor.ca/Documents/residents/planning/plans-and-community-information/windsor-official-plan/Chapter%2010.pdf</u>
- Coder, K. D. (2021, May). *Tree Tolerance of Site Development Activities*. Retrieved from University of Georgia, Warnell School of Forestry & Natural Resources Outreach Publication WSFNR21-45C. 6 pp.: <u>https://bugwoodcloud.org/resource/files/19015.pdf</u>

# APPENDIX

Plan of Survey of Part of lot 1, Registered Plan 1163 (2121 Riverside Drive West)

